المواصفات الفنية الخاصة بالمناقصة العامة رقم المناقصة : (٢٠١١/٦٩)

الخاصة بشراء وتوريد لوحات توزيع كهربائية DC

المؤسسة العامة للاتصالات السلكية واللاسلكية الإدارة العامة للمشتريات والمخازن إدارة المشتريات - قسم العقود والمناقصات



DC Distribution Panel specification:

SCOPE

This specification covers the design, manufacturing supply of Indoor DC Distribution cabinet. For
power supply for telecommunication equipments.

2. The system shall be DC -48 Volts with effectively grounded positive.

SERVICE CONDITIONS

1. Equipment to be supplied against this specification shall be suitable for satisfactory continuous operation under the following conditions.

2. Maximum ambient temperature

(40°C).

3. Relative Humidity

(10 to 90%).

4. Maximum altitude


(2500M above sea level)

Rated voltage:

1. Rated voltage for the Distribution Board, MCBs, bus ways etc. shall be -48V DC.

General requirements:

- The Distribution Board shall be wall mounted/floor mounted having compact design and made of metal.
- 2. The Board shall be closed, dust protected, weather proof and with a special type lining e.g. Neoprene gasket, around the edges of the doors. The distribution board shall comply degree of protection IP.
- 3. Circuit breakers shall be operating vertically upward for ON/OFF operation & shall be suitable and provided with suitable copper busbars.
- 4. All doors shall be provided with mechanical interlocking arrangements along with keys.
- 5. The distribution board shall have no door on rear side.
- 6. Danger board (Caution Plate) shall be fitted suitably on the door of the DB. Danger board shall be of 000x0000 mm size with details.
- Detachable gland plates suitable for receiving the cable shall be provided at the bottom side of Distribution board with glands.
- 8. The ventilating louvers should be covered on inside by a perforated sheet.
- 9. Each Distribution Board shall be provided with:
 - -Name plate showing the details such as manufacturer's name, Sr No., rating etc.
 - -Danger board scripted in English,



DC PANEL

Incoming circuit

Incoming circuit shall have copper busbars (positive and negative polarity) and main circuit breaker (see the Schedule Quantities)

To receive incoming cables positive and negative bolted type connector of suitable size shall be provided.


Outgoing circuits:

Total outgoing circuits shall be provided as per the details given below.

- a) Rated voltage -48VDC.
- b) Rated current (see the Schedule Quantities)
- c) The cabinet enclosure shall be provided with proper earthing arrangement.
- d) Earthing arrangement shall consist of busbar. Bolts of....mm (min.) with 2 spring/ plain washers and 2 check nuts.
- e) PVC cable glands of adequate size shall be provided for all incoming and out going cables.
- f) The copper busbars of positive polarity must be arrangement with suitable connectors

Drawings

 The successful bidder has to supply the complete material as per overall General Arrangement drawing. Successful bidder shall submit the detailed drawings along with component details/makes etc. for necessary approval.



Republic of Yemen

Public Telecommunication Corp.

Tender Board (Technical Board)



المُحَكُورَ لِيَسَى الْمِمْسَى الْمُحَلَّيُ الْمُحَلَّيِ الْمُحَلَّيِ الْمُحَلَّيِ الْمُحَلِّينِ السلكية واللاسلكية لمناقصات

اللجنة الفنية

الرقم : _______التاريخ : _____

جدول الكميات لشراء وتوريد عدد (35) لوحه توزيع كهربانيه DC جدول الكميات لشراء وتوريد عدد (35) الوحه توزيع كهربانيه

إجمالي التكلفة	التكلفة للوحدة	الكمية المطلوبة	القدره	اسم الصنف	م
		20	القاطع الرئيسي 250A /2POLE القواطع الفرعيه صفين تركب على حوامل نوع اوميجا (OMEGA) كل قاطع 1POLE وعدد: 2X80A,8X63A,4X40A,6X32A	لوحة توزيع كهربائيه DC 250A	1
		15	القاطع الرئيسي 400A /2POLE القواطع الفرعية صفين تركب على حوامل نوع اوميجا (OMEGA) كل قاطع 1POLE وعدد: 4X80A,8X63A,6X40A,8X32A	لوحة توزيع كهربانيه DC 400A	2
		35		الاجمالي	116

